ROYALTY CALCULATION

Name of Work : Development of Parks in Paschim county and LM Enclave in Dasarahalli Zone

Sand Filling			
Description	Qty in Cum	Constant	Total Qty
Sand	44.62	0.88	39.27
wet mix macadam			
Jelly	60.42	1.32	79.75
Plain Cement Concrete 1:3:6			
Sand	22.91	0.46	10.54
Jelly	22.91	0.89	20.39
Cement Concrete M-20			
Sand	17.40	0.43	7.48
Jelly	17.40	0.69	12.01
SSM 1:6			
Sand	15.88	0.30	4.76
Size	15.88	1.00	15.88
Solid Kerb			
Sand	281.22	0.017	4.78
Jelly	281.22	0.032	9.00

Sl	Items	Qty	Rate	Amount
1	Jelly	121.15	128	15507
2	Sand	66.83	136	9089
3	Size	15.88	184	2922
			Total	27518

Asst.Engineer

Asst.Executive Engineer
Project Sub Division

Scanned with CamScanner